MYSORE DIVISION.

Dated 12th November 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 5th December 1930, for restoring Honganur Mukanahally Tank, Chamarajnagar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 (one hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Honganur Mukanahally Tank, Chamarajnagar Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted both in figures and words for each item of work.

10. L. S. rates will be rejected.

11. Tendered rates will not be increased at any cost.

12. Non-performance of the contract will entail the forfeiture of earnest money.

Abstract of quantities to be advertised in the *Gazette*.

No.	Items of work.	Per	Quantity
	Bund.		
1	Jungle clearing	Grade	37
2	Cutting grips to bund	,,	37
3	Earthwork to bund with watering and consolidation complete.	C.yd.	7,469
4	Turfing	Sqr.	689·95
5	New grade stones including cutting numbers and painting ...	No.	38
6	New index stones	,,	38
7	Register and date stones do	,,	1
8	Bench mark stones do	,,	2
9	Guage stones	,,	1
	Sluice.		
1	Cut opening bund and refilling with consolidations ...	C.yd.	42
2	Concrete in surki mortar	C.ft.	256
3	Burnt brick in surki mortar	,,	310
4	Stone slabes 6" thick dressed and fixed	S.ft.	70
5	Plastering with surki mortar	Sqr.	1·15
6	C. I. pipe 3" dia including fixing	R.ft.	24
7	Jali wood plug with iron fittings, iron flat bar for locking arrangements, etc.	No.	1
8	Cutting holes in upper and lower orifice slabes	,,	2
	Waste weir.		
1	Earthwork excavating founds and using the same to bund ...	C.yd.	38
2	Rough stone work dry	,,	44

K. NARAYANA IYENGAR,
Executive Engineer.

6 c